BRUHATH BENGALURU MAHANAGARA PALIKE,DASARAHALLI ZONE
Office of Executive Engineer
SCHEDULE -B

Name Of Work: ::Community Property Maintenance including parks in Dasarahalli ward no 15

Sl. No	Description of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.	Cum	12.6	430	
2	Providing and laying in position plain cement concrete Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates 0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications	Cum	6.3	4980	
3	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarseaggregates @ 0.64 cum and fine aggregtes @ 0.43 cum,with superlastiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in laye` not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6.3	5111	
4	Providing & Fixing Granite benches including cost of Materials Labour as per Specification	Nos	14	8598	
5	Disposal of debris to the final place of disposal with all lead and lift and as directions by the Engineer incharge of work. KSRRB M100-1 Loading and Unloading of Stone Boulder I Stone Cum 57.00 aggregates /Sand/ Kanker I Moorum. KSRRB M100-1: Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.	Cum	12.6	65	

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner